

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE -'B'

No:EE/YNK-D/E-PMT/08/2016-17 Dated: 4-03-2017

Item No: 21

Name of Work:-Emergent work in ward No- 01 of yelahanka sub division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Rate	Approved Rates Sr R S THYAGARAJ
1	Removing B.S. slab of Drain and stacking. (P No.25 / I N 5.32)	Sqm	1998.00	59.66	Rupees fifty nine and paise sixty six only
2	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH Chapter 3 (P.142/I.19.1)	Cum	1114.20	79.13	Rupees seventy nine and paise thirteen only
3	Refixing stone slabs of drains and pointing in C.M.(1:3)(P.No.25/I.No.5.33)	Sqm	1698.30	73.30	Rupees seventy three and paise thirty only
4	Providing and fixing RCC precast Slabs of 0.10 m thick of CC 1:2:4 with 20 mm and down size graded granite metal , machine mixed , including cost of all material , labour , HOM of Machinery , curing complete	Sqm	299.70	1911.00	Rupees one thousand nine hundred eleven only
5	KSRRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No. KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3)	Cum	280.01	182.30	Rupees one hundred eighty two nd paise thirty only
6	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1)	cum	1146.71	90.00	Rupees ninety only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Approved Rates Sri R S THYAGARAJ	Rate in Words
7	KSRRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/1.4.3)	Cum	4.52	4694.70	Rupees four thousand six hundred ninety four and paise seventy only
8	KSRRB 15-19.2: Providing and fabricating MS Name boards of size 0.60 x 0.60 mtrs with verticle post of 3.70 height made of two jointly welded 65x65x65mm angles with necessary hold fast weld top, name board of 18 gauge sheet of size 0.09x0.60mtrs welded to angles of 25x25x4mm on all sides with all fabrication charges transportation and other incidental charges (approved rates)	No	60.00	5920.46	Rupees five thousand nine hundred twenty and paise forty six only
9	KSRRB 4-1.7: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs with 20mm and down size graded granite metal coarse aggregate @ 0.84cum and fine aggregate @ 0.56 cum machine mixed concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2,P No. 13 / Item No. 4.7	Cum	11.27	5095.01	Rupees five thousand ninety five and paise one only
10	KSRRB 4-1.7: Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt, and other foreign matter including cost of materials, labour, complete as per specifications (P No. 120/Item No.15.74)	sqm	43.20	79.09	Rupees seventy nine and paise nine only
11	KSRRB M800-9: Painting new letter and figures of any shade with synthetic enamel paint block or any other approved colour to give an even shade complete as per specification, ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) MORTH specification No. 803,(P No. 197 / Item No. 24.9)	Cum	5400.00	0.72	paise seventy two only
12	KSRRB 5.2.3: Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (Page No. 23/ Item No. 5.6)	sqm	11.52	4038.78	Rupees four thousand thirty eight and paise seventy eight only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Approved Rates Sr R S THYAGARAJ	Rate in Words
13	KSRB 15.1.1: Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (Page No.113/Item No. 15.1)	Sqm	19.20	93.56	Rupees ninety three and paise fifty six only
14	Providing and fixing RCC precast Slabs of 0.20 m thick of CC 1:2:4 with 20 mm and down size graded granite metal, machine mixed, including cost of all material, labour, HOM of Machinery, curing complete	sqm	21.60	4095.82	Rupees four thousand ninety five and paise eighty two only
15	Providing and fixing to wall, ceiling and floor, high density polyethylene pipes 6.00 kgs/sq.cm working pressure 75mm outside diameter raising mains & exposed distribution pipes with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost all material, labour charges, HOM of equipments and testing complete as per specifications. (P.N. 94 I.N 13.73.4)	Rmtr	400.00	291.30	Rupees two hundred ninety one and paise thirty only
16	Providing and fixing to wall, ceiling and floor, medium density polyethylene pipes 6.00 kgs/sq.cm working pressure 50mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost all material, labour charges, HOM of equipments and testing complete as per specifications. (P.N. 93 I.N 13.70.1)	Rmtr	150.00	249.68	Rupees two hundred forty nine and paise sixty eight only
17	Refilling available earth around pipelines, cables in layers not exceeding 20cms in depth compacting each deposited layers by ramming after watering lead upto 50m and lift upto 1.5m including cost of labour complete as per specification (P. No.6 I.No.2.11)	Cum	247.50	72.40	Rupees seventy two and paise forty only
18	KSRB 13-6.3.1: Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 50 mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6 / 13.3 (Page No.91/Item No.13.37)	Each	4.00	1995.66	Rupees one thousand nine hundred ninety five and paise sixty six only
19	Providing and fixing on position brass bib cock of approved quality 25mm dia nominal bore including cost of all materials labour and HOM of equipments with all leads complete as per specifications. (P.N.91 I.N 13.25)	Each	12.00	272.37	Rupees two hundred seventy two and paise thirty seven only

Signature of the Contractor

Narayana
Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.